



OBSERVATION

Coronavirus, as in most of the world, is expanding on the African continent. As of March 30, 2020, 46 of 52 African countries have been affected by the virus. This announced crisis has many facets and confirms to us how necessary a rapid, united and adapted health approach is.

Thus, in order to strengthen health systems, we propose to government authorities, to NGO and to other private entities, to deploy temporary and adapted medical infrastructures with a concept of independent modules as: a testing area, an hospitalization area (for observation, standard, or for intensive care), together with additional modules used to create a hospital environment (laboratory, X-Ray, morgue, ...), with a possible autonomy (power, water,...).

There is not one Africa but "Africas". The deployment of emergency health infrastructures must be supported by competent players capable of understanding the needs of each country, each city.

PROPOSAL

GL events, an international group present in South Africa and in Dubai, associated with QGM Holding, expert in the deployment of health services in Africa, would like to offer you our services:

a solution of turnkey medical modules including medical equipment, and operational as soon as possible.

Our modular infrastructure concept has several advantages because it can be installed, "à la carte", to match your needs:

- On a bare surface, independently
- In addition to an existing hospital or medical infrastructure
- Possibly within an existing infrastructure such as a stadium or gymnasium

Our priority is to participate in your fight against the virus but also to offer you health solutions that could adapt to your health infrastructure in post-crisis periods.

SOLUTION

A Covid-19 infrastructure is characterized by two areas:

- A triage area and possibly a temporary hospitalization area which must respect the containment rules and be subject to careful disinfection.
- A Covid-19 zone where positive patients are gathered. Protective measures are mainly supported by the care staff.

According to the needs, we can create different modular structures ranging from a testing centre (sorting, prevention, distribution of basic necessities) to the creation of a real temporary hospital dedicated to Covid-19.

The modular aspect therefore offers a panel of solutions adapted to your needs and to the health organization already in place in the field. This easily transportable solution guarantees you a great reactivity. These modules must be independent in order to meet the various evolving needs:



Testing Module



Hospitalization Module



Unit Module



Intensive Care Operating Theater Module



X-Ray or **Scanner Module**



Cloakroom, sanitary, shower module



Morgue Module



Technical Module (power, water..)



MODULES

Reception Drive

Welcome desk
and office equipment x1
Sampling booth x1
Treatment trolley (drive) x1

Testing Module

Stretcher with gallows x5
Blood pressure monitor x5
Stethoscope x5
Treatment trolley x5
Thermometer x5
Glucometer x5
Examination Lamp x5

Temporary Hospitalization

Bed with gallows x5
Nocolysis (diffusion apparatus) x2
Independent oxygen generator
(20L/min) x1



Microscope x1
Hematology analyzer x1
Biochemistry Analyzer x1
Device ESR x1
Urine Analyzer x1
Centrifuge x1
Incubator x1
Glucometer x1
Laboratory Stool x1
Blood product refrigerator x1
Refrigerator for medicines x1
Covid PCR test / Rapid test x1



X-ray apparatus
mobile digital x1
Service trolley x1
Lead Apron x1
Protective equipment
for staff x2
Portable Ultrasonic Device x1
Scanner (option) x1
Screen x1



MODULES

Operations Theater

Operating table x1 Scialytic x1 Anesthesia workstation x1 (with fan and monitor) Electrocautery equipment x1 Hand-held electrode defibrillator x1 AED Consumer Defibrillator x1 Infusion set and of syringe pumps x3 General purpose instrument x1 Orthopaedic Surgical Set x1 Medical Waste Box x1 Double bowl on stand x1 Suction x1 Stainless steel sink x1 Storage cabinet x1 Steam Sterilizer x1 Autoclave x1

Hospitalization By Module

Beds **x10**Shelves **x10**Infusion stand **x10**

Intensive Care Unit by Module

Critical Care Beds x6
Treatment trolley x2
Defibrillator x1
Intubation Set x6
Tracking Monitor x6
Infusion set
and syringe pumps x6
Respirator x6
Suction device x2
ECG unit x1

Morgue

Fridge (4 bodies) **x3**Washing table **x1**

Technical Module

Mobile air conditioning unit x1
Bottle filling system generator
oxygen individual oxygen x1
Generator O2
Water treatment
Control Panel

Laundry

Sanitation change room showers

O2 Production plant

Incinerator

Catering Lounge





Ultrasonic cleaner x1


EXAMPLES:AUTONOMOUS MEDICAL STRUCTURES COVID-19

All modules are completely autonomous and can be selected individually or in combination

Example no.1: Proximity structure

The aim of these structures is to offer prevention, screening and temporary care before transfer. They are composed of a reception, a testing centre, a small temporary hospitalization, a prevention centre and the supply of basic necessities to the population (mask, gel, gloves, water, food).





N°	Name	Number
1	Drive Home	1
2	Sorting module	1
3	Temporary hospitalization	1

QGM Holding is also able to provide:


FSP1, FSP2, 3PLIS surgical masks, protective visor, protective gown, gloves, hydroalcoholic gel, Covid-19 PSR / rapid test





Cnr Nasrec & Randshow Road, Johannesburg, 2000 South Africa Head Office: (Johannesburg) - tel: +27 11 210 2500, fax: +27 11 680 9940 Branches: (Cape Town) - tel: +27 21 526 3200, fax: +27 21 552 1841 (Durban) - tel: +27 31 579 3255, fax: +27 31 563 3244 www.gl-events.co.za

COVID-19 MARQUEES_VIRUS TESTING UNIT_REV000




Layout - Furniture

CODE	DESCRIPTION	QTY
Basin	Basin - Plumbing	1
H01a	Office Chair	2
H08	Eddy Office Chair	1
H107a	Flat Shelves	20
H107a	Flat Shelves	2
H121	Locker Unit	2
sink	Plumbing	1
Step Down Counter		1
(No Fascia)		
Triage Bed		5
(Specification TBC	by	
Supplier)		
Haz Waste Bin		2
Cleaning Cart		1

EXAMPLES: AUTONOMOUS MEDICAL STRUCTURES COVID-19


All modules are completely autonomous and can be selected individually or in combination

Example n°2: Complete structure Covid-19 for 100k/150k inhabitants



N°	Name	Number
1	Drive Home	1
2	Sorting module	2
3	Temporary hospitalization	2
4	Laboratory	1
5	, Radiology	1
6	Operating theatre	1
7	Hospitalization by module	9
8	UCI by module	2
9 /10	Cloakroom/Sanitary/Shower	1
11	Catering/Relaxation	1
12	Lingerie	1
13	Waste incinerator	1
14	Morgue	1
15	O2 power plant	1

FOOTBALL PITCH BOUNDARY



GENERAL WARD BEDS: 90 L.C.U WARD BEDS:12 EMERGENCY WARD BEDS: 10 TRIAGE BEDS: 10 SHOWERS: 4 TOILETS: 29 WASH BASINS: 21 SLUICE ROOM I WASH ROOM 2 WORKSTATION: 4 40" CONTAINERS: 7 20" CONTAINERS: 4 CORRIDOR STORAGE UNITES: 6 0 ENTRANCE / CANOPEE ATTENTE 1 RECEPTION / ACCEUIL/ DRIVE 2 VIRUS TESTING UNIT (TRIAGE) / MODULE DE TRIAGE 3 EMERGENCY WARD / HOSPITALISATION PROVISOIRE/ SANIT 5 RC SCANNER / RADIO CONVENTIONNEL + SCANNER 6 SURGERY MODULE / BLOC OPERATOIRE RECOVERY / STE + PRE OP + POST OP/ SANIT 7 GENERAL WARD / HOSPITALISATION COVID/ SANIT 8 L.C.U / UNITE SOIN INTENSIF 9 SANITARY + WARD BATHROOM / VESTIAIRES/ SAS/ SANIT/ DOUCHES 10 DINING QUARTERS / RESTUARATION/ LAVERIE/ DETENTE 11 STAFF ENTRANCE (MALE + FEMALE) / ENTREE DU PERSONNEL (HOMME ET FEMME) 12 LAUNDRY / LINGERIE 13 WASTE DISPOSAL / DECHETS/ INCINERATEUR 14 MORTUARY / MODULE MORGUE 15 O2 STORAGE / PLATFORME O2

DEPLOYMENT PLANNING

EMERGENCY SOLUTION - DEPLOYMENT PLANNING FOR A TESTING MODULE

Activities	Week 1	Week 2	Week 3	Week 4	Week 5	Week 6	Week 7	Week 8	Week 9	Week 10
Confirmation										
Site Adaptation - Design										
Medical equipment needs definition for immediate purchase order										
Confirmation equipment and infrastructure preparation										
Transport (plane)										
Infrastructures and medical equipment installation										
Operation										
Dismantling (after X month of rental)										

EMERGENCY SOLUTION - DEPLOYMENT PLANNING FOR HOSPITAL INFRASTRUCTURE

Activities	Week 1	Week 2	Week 3	Week 4	Week 5	Week 6	Week 7	Week 8	Week 9	Week 10
Confirmation										
Site Adaptation - Design										
Confirmation equipment and infrastructure preparation										
Transport (plane)										
Infrastructures and equipment installation										
Operation										
Dismantling (after X month of rental)										

Deployment: subject to availability of medical equipment Final offer: according to the conceptualization of request



REFERENCES











- Electrical distribution Military Hospital France
- Air-conditioning for temporary hospital Brazil
- **Temporary polyclinic** Olympic Games Rio 2016 *Brazil*
- Base Camp for Chilean Army and Chilean Police *Chile*
- Base Camp for the French Ministry of Defence and
 Infrastructure Directorate Kabul, Afghanistan
- Base Camp for the French Ministry of Defence and
 Infrastructure Directorate Bangui, Central-African Republic
- Temporary **Hospital** for the Chilean Airforce *Chile*
- Temporary **Hospital** for the Chilean Army *Chile*
- Base Camp for the French Ministry of Defence and
 Infrastructure Directorate Lebanon & Gabon
- Aid Station Chile



Jean-Guillaume LACOSTE

GL events Middle East – CEO

United Arab Emirates

Mob: +971 50 306 7252

jean-guillaume.lacoste@gl-events.com

Maxime ROSENWALD

GL events South Africa – Managing Director

South Africa

Mob: +27 60 508 7713

maxime.rosenwald@gl-events.com

Docteur Quentin GAUDISSART

QGM Holding Co-founder & CEO

Belgium

Mob:+32 495 20 00 07

q.gaudissart@qgm-ms.com

Gwen MARIEN

QGM Holding Co-founder

France

Mob :+33 6 89 53 75 03

g.marien@qgm-ms.com

