



**ADVERTISEMENT OF MANIFESTATION OF INTEREST
VESSELS SUPPLIES FOR OFFSHORE INSTALLATION CAMPAIGN**

Reference: TJSSUB06
Location: Mozambique

1. OBJECTIVE OF THE WORK

CORAL SOUTH DEVELOPMENT Project has the objective to exploit the southern portion of the Coral non-straddling reservoir through one Floating LNG (FLNG) Unit, and relevant subsea development.

As part of the project and due to the installation phase, TP Mozambique LDA intends to invite interested parties in Mozambique for the Supply of Vessels hereafter referred to as the Services. This Services will be carried out to help in our installation team in the Offshore Campaign.

2. MAIN RESPONSIBILITIES

The scope of work of **Supplies of Vessels** for offshore installation campaign of CORAL SOUTH Project is summarized as follow:

Vessel to be Supplied	Qty	Description	Campaign period
Cargo Barge and Tug	2	Cargo Barge minimum requirement: <ul style="list-style-type: none"> Min. 2500m² of clear deck space Min. length 300 ft Min. deck capacity 10Te / m² for landing structure on board Tug Minimum requirement: <ul style="list-style-type: none"> DP-Class: 2 Average speed: Min. 5 knots Bollard Pull: Min. 80Te 	1 Cargo and 1 Tug: Needed in Q1 and Q2 2021, exact date to be confirmed
			1 Cargo and 1 Tug: Needed in Q2 and Q3 2021, exact date to be confirmed
Platform Supply Vessel (PSV1)	1	<ul style="list-style-type: none"> Deck space: Min. 1000 m² DP-Class: 1 or 2 Average speed: Min. 10 knots Min deck capacity 5 Te / m² with T-bars aligned with frames Gangway and Boat landing structure on board Internet access 512 kbps with Wi-Fi access. 	Q1 and Q2 2021, exact date to be confirmed
Platform Supply Vessel (PSV2)	1	<ul style="list-style-type: none"> Deck space: Min. 1000 m² DP-Class: 1 or 2 Average speed: Min. 10 knots Min deck capacity 10 Te / m² with T-bars aligned with frames Gangway and Boat landing structure on board Internet access 512 kbps with Wi-Fi access. 	Q1 and Q2 2022, exact date to be confirmed
Light Construction Vessel	1	Base Case: For works linked to Flexible & Umbilical Clump Weight <ul style="list-style-type: none"> 49 t Lifting capacity @ 22 m of radius Crane able to reach 2, 300 m 2 Work ROVs 	Q1 and Q3 2021, exact date to be confirmed
		Option 1: For works linked to Well Head Jumper <ul style="list-style-type: none"> 123 t Lifting capacity Hook Height 36 m @ 22m radius Crane able to reach 2, 300 m 2 Working ROVs 	

3. REQUIREMENTS

- Written confirmation indication of your interest in submitting a bid for the said Services either in part or in Full;
- A description of your company capability and field of expertise;
- Past experience in a similar type of work in Mozambique and around the World.

Notes:

- Should you be considered as a bidder, you would be receiving the call for bid in 22nd May, 2020 and will be requested to provide your offer one month later;
- It is expressly understood that this Request of Interest shall not force TP Mozambique LDA to send a call for bid or otherwise commit itself to your company.